


NOTES:

- 1. TRENCH WIDTH "W" SHALL BE 40" MINIMUM FOR 15" DIAMETER AND SMALLER PIPES AND 1 1/2 TIMES THE INSIDE DIAMETER PLUS 18" MINIMUM FOR 18" AND LARGER PIPES.
- 2. 5/8" CRUSHED SURFACING TOP COURSE BACKFILL MATERIAL REQUIRED ON SMALL TRENCH REPAIR UTILITY PROJECTS, UNLESS DIRECTED OTHERWISE BY THE ENGINEER. FOR CITY OF RICHLAND CAPITAL IMPROVEMENT PROJECTS AND SUBDIVISIONS SECTION 7-08 OF THE WSDOT STANDARD SPECIFICATIONS SHALL APPLY.
- 3. HMA PATCH LIMITS SHALL MEET THE REQUIREMENTS OF RICHLAND MUNICIPAL CODE 12.08.065. MINIMUM 6 FT WIDE.





TRENCH DETAIL

| PUBLIC WORKS ENGINEERING | |
|---------------------------|-------------|
| APPR. BY: PKR | DATE: 02.22 |
| DRAWN BY: LD | DWG: U2 |
| CAD FILE: 2014_U2_02_2022 | |